



NOTES:

1. FINISH FLOOR ELEVATION AT BUILDINGS 1000 AB + 941'00"
2. FINISH FLOOR ELEVATION AT BUILDINGS 2000 A = 951'08"
3. FINISH FLOOR ELEVATION AT BUILDINGS 3000 + 962'84"
4. FINISH FLOOR ELEVATION AT BUILDING 4000 + 973'38"
5. FINISH GRADE AT BUILDING ENTRANCES SHALL BE NO GREATER THAN 12" BELOW FINISH FLOOR
6. PROVIDE MIN 2" E/J BETWEEN THIN BRICK AND MODULAR BRICK
7. WHERE SLAB EDGE @ STOREFRONT IS EXPOSED, PROVIDE BREAK MATEL TO MATCH
8. TO EXCEED ALL SPECIFICATIONS, PROVIDE 1/2" MODULAR BRICK
9. GC TO PAINT ALL BOLLARDS IN PARKING/LOADING AREA, COLOR TBD
10. BRICK CONTROL JOINTS AS SHOWN. WHERE NOT SHOWN, G/C SHALL NOT EXCEED 24" MAX
11. NO VENTS WITHIN 4" OF ALL BUILDING FIRE WALLS
12. NO WINDOWS WITHIN 2'-0" (2'-0") OF ALL BUILDING FIRE WALLS. - SEE A5-06
13. SEE 57-01 FOR WINDOW LOADS
14. IN WHITE (OR LIGHT COLOR) HARDWARE PANELS, WINDOWS TO BE DARK BRONZE
15. IN DARK COLORED HARDWARE PANELS, WINDOWS TO BE CLEAR ANODIZED
16. IN HARD METAL, REVEAL AROUND WINDOWS. DO NOT INSTALL BRICK MOLD TRIM AROUND WINDOWS INSET IN HARDWARE PANELS UNLESS APPROVED BY OWNER
17. PROVIDE 5/8" BRICK MOLD TRIM ABOVE, IF APPROVED BY OWNER
18. PROVIDE 5/16" HARDSET TRIM BETWEEN ALL BALCONY BARS AND TRIPLE WINDOWS

SOUTH TERRACES
115 PERIMETER CENTER PLACE, SUITE 950
ATLANTA, GEORGIA 30346
TELEPHONE: 770 396 7248
FAX: 770 396 2945



FCR



ISSUES & REVISIONS	DATE
CONCEPTUAL DESIGN	08/21/2015
PROGRESS SET	09/02/2015
SCHEMATIC DESIGN	09/28/2015
GMP/DESIGN DEVELOPMENT	10/15/2015
FOUNDATION PACKAGE	12/07/2015
GMP	04/03/2017
PERMIT SET	05/22/2017
3. BUILDING PERMIT	07/25/2017

30X42 © 2017 The Preston Partnership, LL

