

NOTES:

1. SEE SHEET M3.XX FOR APARTMENT HVAC.

2. UNLESS NOTED OTHERWISE, ALL CEILINGS ARE PART OF A RATED FLOOR/CEILING ASSEMBLY, AND REQUIRE A CEILING RADIATION DAMPER (CRD) AT EACH PENETRATION OF CEILING.

3. FOR MECHANICAL SYSTEMS SERVING THE CORRIDORS, THE O.A. INTAKE LOUVER SHALL BE INSTALLED A MINIMUM OF 10'-0" FROM APARTMENT UNITS TOILET EXHAUST. ADJUST TERMINATION POINT OF EXHAUST DUCTS AS NECESSARY FOR EACH APARTMENT UNIT.

4. ALTERNATE ROUTING OF DRYER AND TOILET EXHAUST DUCT IN APARTMENT UNITS SHOWN HERE, TO AVOID CONFLICT WITH 10'-0" CLEARANCE REQUIREMENT FROM CORRIDOR OUTDOOR AIR INTAKE.

5. APARTMENT UNIT WINDOWS OPEN SO THAT THE TOP OF OPENING IS AT 5'-0" A.F.F. EXHAUST TERMINATIONS ARE LOCATED ABOVE THE CEILING OF APARTMENTS WHICH IS LOCATED AT 9'-0" A.F.F. THIS CREATES A MINIMUM 4'-0" CLEAR FROM BUILDING OPENING TO A VENT CAP.

KEY NOTES:

1 TOILET EXHAUST OUTLET.

2 DRYER EXHAUST VENT OUTLET.

(3) O.A. INTAKE INLET. MAINTAIN 10'-0" FROM ANY EXHAUST OUTLET AS SHOWN ON THESE PLANS.

THE PRESTON PARTNERSHIP, LLC A MULTI-DISCIPLINARY DESIGN FIRM

SOUTH TERRACES 115 PERIMETER CENTER PLACE, SUITE 950 ATLANTA, GEORGIA 30346 TELEPHONE: 770 396 7248

WWW.THEPRESTONPARTNERSHIP.COM

FAX: 770 396 2945



REVEL AT THE BALLPARK PHASE II

2885 CRESCENT PKWY SMYRNA, GA 30080



ATLANTIC REALTY **PARTNERS** 

3438 PEACHTREE ROAD **SUITE 1425** ATLANTA, GA 30326

ISSUES & # - REVISIONS \_\_\_\_\_ 8/21/15 09/28/15 10/14/15 12/07/15 04/03/17 05/22/17 CONCEPTUAL DESIGN SD PROGRESS SET

GMP PRICING SET FOUNDATION PACKAGE

GMP PACKAGE
PERMIT SET

05/22/2017 1493101

BUILDING 1000A PROJECT -LEVEL 4

M1-14A

30X42 © 2017 The Preston Partnership, LLC