

<u>NOTES:</u>

1. SEE SHEET M3.XX FOR APARTMENT HVAC.

2. UNLESS NOTED OTHERWISE, ALL CEILINGS ARE PART OF A RATED FLOOR/CEILING ASSEMBLY, AND REQUIRE A CEILING RADIATION DAMPER (CRD) AT EACH PENETRATION OF CEILING.

3. FOR MECHANICAL SYSTEMS SERVING THE CORRIDORS, THE O.A. INTAKE LOUVER SHALL BE INSTALLED A MINIMUM OF 10'-0" FROM APARTMENT UNITS TOILET EXHAUST. ADJUST TERMINATION POINT OF EXHAUST DUCTS AS NECESSARY FOR EACH APARTMENT UNIT.

4. ALTERNATE ROUTING OF DRYER AND TOILET EXHAUST DUCT IN APARTMENT UNITS SHOWN HERE, TO AVOID CONFLICT WITH 10'-0" CLEARANCE REQUIREMENT FROM CORRIDOR OUTDOOR AIR INTAKE.

5. APARTMENT UNIT WINDOWS OPEN SO THAT THE TOP OF OPENING IS AT 5'-0" A.F.F. EXHAUST TERMINATIONS ARE LOCATED ABOVE THE CEILING OF APARTMENTS WHICH IS LOCATED AT 9'-0" A.F.F. THIS CREATES A MINIMUM 4'-0" CLEAR FROM BUILDING OPENING TO A VENT CAP.


KEY NOTES

1) TOILET EXHAUST OUTLET.

② DRYER EXHAUST VENT OUTLET.

3 O.A. INTAKE INLET. MAINTAIN 10'-0" FROM ANY EXHAUST OUTLET AS SHOWN ON THESE PLANS.

KEY PLAN





THE PRESTON
PARTNERSHIP, LLC
A MULTI-DISCIPLINARY DESIGN FIRM


SOUTH TERRACES

115 PERIMETER CENTER PLACE, SUITE 950 ATLANTA, GEORGIA 30346

TELEPHONE: 770 396 7248

WWW.THEPRESTONPARTNERSHIP.COM

FAX: 770 396 2945





PROJECT

REVEL AT THE BALLPARK PHASE II
2885 CRESCENT PKWY

SMYRNA, GA 30080

| ATLANTIC | REALTY

ATLANTIC REALTY PARTNERS

3438 PEACHTREE ROAD SUITE 1425 ATLANTA, GA 30326

SSUES & #\ REVISIONS	D.
CONCEPTUAL DESIGN	8/21/15
SD PROGRESS SET	09/28/15
GMP PRICING SET	10/14/15
FOUNDATION PACKAGE	12/07/15
GMP PACKAGE	04/03/17
PERMIT SET	05/22/17

DATE -	
	05/22/201
JOB NUMBER	
	149310
DRAWN BY	149510
DRAWN BY	1 [
CHECKED BY	
	CMC
	CIVIC
SHEET TITLE	•

BUILDING 2000 PROJECT -LEVEL 6

M1-26

30X42 © 2017 The Preston Partnership, LLC