



- FOUNDATION NOTES:**
1. SLAB ON GRADE SHALL BE 4" THICK CIP CONCRETE REINF W/ 6x6-W2.1xW2.1 LOCATED 1/2" CLEAR FROM THE T/SLAB. TOP OF S.O.G. ELEVATION = F.F.E. PER ARCHITECTURAL DRAWINGS.
 2. SEE 12/S5-01 FOR CONSTRUCTION JOINTS. SPACE JOINTS AS REQ.
 3. ALL FOOTINGS AND THICKENED SLABS SHALL BE CENTERED ON WALL ABOVE. U.N.O. (UNLESS NOTED OTHERWISE).
 4. ALL DIMENSIONS ARE TO EDGE OF SLAB OR FOOTING CENTERLINE U.N.O. ALL DIMENSIONS SHALL COORDINATE WITH ARCHITECTURAL DIMENSIONAL CONTROL PLAN.
 5. SEE ARCHITECTURAL FOR ALL EXTERIOR SLAB AND CURB INFORMATION.
 6. F# DENOTES FOOTING DESIGNATION. SEE FOOTING SCHEDULE FOR FOOTING SIZE AND REINFORCING.
 7. → DENOTES FOOTING STEP. SEE 10/S5-02 FOR ADDITIONAL INFORMATION.
 8. ALL EXTERIOR SPREAD FOOTINGS SHALL BE (-)1'-4" BELOW LOWEST ADJACENT FINISHED FLOOR U.N.O. ALL INTERIOR SPREAD FOOTINGS SHOULD HAVE T/FTG = (-)1'-0" BELOW LOWEST ADJACENT F.F.E. (U.N.O.).
 9. WHERE INTERIOR THICKENED FOOTINGS ADJOIN EXTERIOR FOOTINGS DROP BOTTOM OF INTERIOR FOOTING TO MATCH EXTERIOR. SLOPE BOTTOM OF FOOTING AT 2 HORIZ. TO 1 VERT.
 11. SEE 20/S5-02 FOR SITE WALL DETAIL.
- DENOTES COLUMN TYPE, SEE SCHEDULE ON S3-00
 ○ DENOTES FOOTING
 ○ DENOTES TOP ELEVATION OF FOOTING
 ○ DENOTES CONCRETE PILASTER (WHERE APPLICABLE)
 ○ DENOTES MOMENT CONNECTION BASEPLATE, SEE 11/S6-31
8. WHERE ADJACENT SPREAD FOOTINGS OVERLAP, PROVIDE CONTINUOUS REINF.
 9. ADD'L REINFORCEMENT REQUIRED AT SHEARWALL ANCHOR LOCATIONS PER DETAIL 15/S5-02. SEE S4-XX FOR LOCATIONS AND SCHEDULES.

FOOTING SCHEDULE		
FOOTING	SIZE	REINF.
F3.0	3'-0"x3'-0"x1'-0"	4-#4 E.W.
F4.0	4'-0"x4'-0"x1'-0"	4-#5 E.W.
F5.0	5'-0"x5'-0"x1'-2"	5-#6 E.W.
F6.0	6'-0"x6'-0"x1'-4"	5-#6 E.W.
F6.9	6'-0"x9'-0"x1'-0"	7-#6 E.W.
F7.0	7'-0"x7'-0"x1'-6"	6-#7 E.W.
F8.0	8'-0"x8'-0"x1'-9"	6-#7 E.W.
F9.6	9'-0"x6'-0"x1'-6"	6-#6 E.W.

BUILDING SUMMARY - LEVELS						
PROJECT LEVEL	FFE	BLDG 1000	BLDG 2000	BLDG 3000	BLDG 4000	PARKING DECK
9	1026'-9 1/4"					5
8	1016'-1 3/8"					4
7	1005'-5 1/2"			5	3	6
6	994'-9 9/16"	5	5	4	2	5
5	984'-0 1/2"	4	4	3	1	4
4	973'-3 3/8"	3	3	2	B	3
3	962'-8 1/4"	2	2			2
2	951'-9 9/16"	1	1			DRIVE UNDER
1	941'-0"	B				




1 BUILDING 3000 LEVEL 2 FOUNDATION PLAN
 S1-31 SCALE: 1/8" = 1'-0"



THE PRESTON PARTNERSHIP, LLC
 A MULTI-DISCIPLINARY DESIGN FIRM
 SOUTH TERRACES
 115 PERIMETER CENTER PLACE, SUITE 950
 ATLANTA, GEORGIA 30346
 TELEPHONE: 770 396 7248
 FAX: 770 396 2845
 WWW.THEPRESTONPARTNERSHIP.COM
 CONSULTANT

m²
 STRUCTURAL
 887 West Marietta St. NW
 Suite T103
 Atlanta, GA 30318
 www.m2structural.com
 404-829-2612



PROJECT
REVEL AT THE BALLPARK
 2885 CRESCENT PKWY
 SMYRNA, GA 30080



ATLANTIC REALTY PARTNERS
 3438 PEACHTREE ROAD, SUITE 1425
 ATLANTA, GA 30326
 404-591-2900
 △ ISSUE DATE

SCHEMATIC DESIGN SET	08/28/2015
03 PROGRESS SET	10/07/2015
05/GMP	10/13/2015
FOUNDATION PERMIT	12/07/2015
75% CDs	01/28/2016
GMP SET	04/03/2017
PERMIT SET	05/22/2017

DATE 05/22/2017
 JOB NUMBER 1493101
 DRAWN BY CTK
 CHECKED BY JWS
 SHEET TITLE

BUILDING 3000 LEVEL 2
 FOUNDATION PLAN
 SHEET NUMBER

S1-31
 COMMENTS RELEASED FOR CONSTRUCTION
 © 2014 © 2015 The Preston Partnership, LLC